

Section	Number	Issue	Spec Pages/Sections Modified	Detail Sheets Modified
---------	--------	-------	------------------------------	------------------------

TABLE OF CONTENTS

Table of Contents		All necessary changes; Details table of contents moved to front of details section	all pages	
-------------------	--	--	-----------	--

DIVISION 0 - BIDDING AND CONTRACT REQUIREMENTS

Advertisement For Bids	00010	Updated City contact, online contract document location	all pages	
Instructions to Bidders	00100	Added requirement of registration in SAM	sections 3.0, 19.3, 28.0	
		Added failure to bid on all alternates as reason for rejection	19.3N	
		Added unemployment/workers' comp insurance requirements	new section 22 inserted	
Bid Form	00300	Added SAM requirement to submittal of bid	section 10d	
		Removed "at least 1" requirement from "similar projects under contract"	p. 6	
Bid Bond	00410	Fixed header & footer	all pages	
Agreement	00500	Several minor corrections, format changes	all pages	
		Instructions to Bidders added to list of contract documents	article 8.8	
Performance & Labor + Materials Payment Bonds	00610 & 00620	Fixed formatting	4th line, p. 1	
General Conditions	00700	Updated from 2002 version to 2013 version	whole section	
Supplementary Conditions to the General Conditions	00810	Updated for 2013 EJDC	whole section	

DIVISION 1 - GENERAL REQUIREMENTS

Coordination	01040	Added 7 day/3 day timeline for utility removal, trenching coordination	1.03, last 2 paragraphs	
		Added 90 dBA noise limit for pumps	1.04, last paragraph	
		Added request for extending working hours must be written	1.05, 1st paragraph	
		Scheduling requirements added/clarified	1.06	
		Added MMBP section to include work schedule and coordination pay item	new Part 2	
Field Engineering	01050	Changed requirement from 3 blue tops per station to 5	1.01A, 4th paragraph	
		Added Wyoming PLS requirement	new 1.01C	
		Added MMBP for new construction staking pay item	new Part 2 replacing 1.05	
Permits	01060	Added City licensure requirement for contractor superintendent	new 3rd paragraph	
Submittals	01300	Changed submittal requirements to just 1 electronic (no paper)	section 3.01A	
		Fixed submittal form to "specification" all on one line	p. 5	
Quality Control	01400	Added timelines for submitting test results to engineer	1.02	
Temporary Controls	01560	4 hrs for water service to be cut off, not 6	Section 3.02D	
		Added more detail to mud cleaning requirement	3.03E	
		Added miscellaneous waste to be cleaned	new 3.03G	
		Modified "road maintenance during shutdowns," included winter shutdowns	3.09	
Field Offices and Sheds	01590	Added field office location needs not to interfere, and to be approved by owner	1st paragraph	
		Added more detail on temporary sanitary facilities required	2nd paragraph	
Material and Equipment	01600	Added locating stored material within traffic control area, protecting from damage	1.02	
Contract Closeout	01700	Added description of record drawings required	1.03A	
		Added restore/replace what has been damaged/removed after substant. comp.	3.03, new 3rd paragraph	
Operation and Maintenance	01730	Changed number of copies required to 1 electronic, 1 binder; fixed header	p. 2	
Special Provisions	01750	Added template for Special Provisions	new section	

DIVISION 2 - SITE WORK

Temporary Traffic Control	02060	More detailed requirements for traffic control planning, signage for businesses	3.01, new first 3 paragraphs	
Clearing and Grubbing	02110	Added tree removal/stump removal pay items; provide cover when chipping	3.01 4th paragraph, 4.01, 4.02	
		Added licensure with City requirement for contractor tree removal	3.01 1st paragraph	
		Added City landfill requirements for trees, limbs and stumps	3.01 2nd paragraph	
Trenching, Backfilling and Compacting	02221	Changed dimension in trench excavation sect. from 1' to 6" for consistency w/ std. dwg.	3.04B, 4.01.A.1.	
		Added Dry Utilities Trenching subsection and pay items	3.10, 4.01, 4.02	
Flowable Fill	02228	Changed 2 sacks to 1 sack to make consistent with 03010.	3.01B	
Demolition of Existing Surfacing	02440	Added information on asphalt and concrete disposal	3.01B	

		Added pay items for concrete removal, asphalt removal, sawcutting	4.01, 4.02	
Grading	02540	Added re-test before next lift if: passed compaction test, conditions change	3.02A last paragraph	
Topsoil	02460	Changed to 1" max rock size, define depth as 4" not 6", revised topsoil definition to make more descriptive	2.01A, 3.03A, 3.03B	
Reclamation	02480	Same as above	2.03	
		Added subsection on irrigation conduit and pay items	2.06,3.04,4.01,4.02	
		Added requirements concerning landscaping materials to be replaced by sod	3.03B, new 2nd&3rd paragraph	
		Added requirements for irrigating previously irrigated areas, trees and shrubs	3.03G, new last 2 paragraphs	
Landscaping	02490	Added landscaping section including tree planting	new section	new dwgs 02490-3.02A, -3.02C
Gravel Alley Restoration and Maintenance	02510	Added new section	new section	
Crushed Aggregate Base Course	02519	Added re-test before next lift if: passed compaction test, conditions change	3.09B, new last paragraph	
Asphalt Pavement	02525	Changed font to bold for all testing results from previous day's paving are completed prior to start of next day's production	3.02	
		Added temp. asphalt pay item 02525.30	4.01 & 4.02	
		Added split sampling requirement	3.02B	
Chip Seal	02527	Added chip seal section	new section	
Paint Striping	02530	Added section on pedestrian crosswalks	new subsection 3.04	new dwg 02530-3.04, revised dwgs 02605-3.01d, 02605-3.01e
		Added pay item for broken yellow center stripe 02530.01	4.01 & 4.02	
		Changed measurement unit for ped crossing stripes from (EA) to (SF) 02530.12	4.01 & 4.02	
		Changed 02530.13 from "solid white chevrons" to "solid chevrons", from (EA) to (SF)	4.01 & 4.02	
		Added 02530.18 solid white bicycle lane stripe (LF)	4.01 & 4.02	
Pre-formed Pavement Markings	02540	Added new thermoplastic striping including bike lane & ped crosswalks	new section	see new/revised dwgs for section 02530 above
		All pay item changes for 02530 also mirrored in 02540	4.01 & 4.02	
Adjusting Street Fixtures	02570	Changed concrete collars (diamonds)--not required in pavement except as corrective. Required in non-paved areas, with pay item	3.01G, 4.01 & 4.02	revised dwgs 02570-3.01a, 02570-3.01b, 02722-3.02
Street Signs, Utility Poles, and Mailboxes	02605	Revised standard details on flashing signs		revised dwgs 02605-3.01d, 02605-3.01e
Relocate Fence	02620	Added content and pay item for temporary fence	1.01A, 2.01D, 3.01E, 4.01&4.02	
Valves and Valve Boxes	02641	Added valve box adaptor, included in valve payment item	2.01C, 3.02, 4.02A.1.	revised dwgs 02641-2.01b and 02641-2.01d to show adaptor
		Added header and footer	all pages	
		Added pay item for concrete collar (still #02570.50), removed collar as included with valve payment	4.01 & 4.02	
		Changed valve box from slip type to screw type	2.01B	
Fire Hydrants	02644	Removed hydrant re-installation detail	section reduced to 4 pages (spacing) but no text changes	removed dwg 02644-2.01b
Water Service Lines and Appurtenances	02645	Added new pay item for x" curb stop/box, removed curb stop as included with x" water service line pay item	4.01&4.02	
Water Main	02710	Added a spec for water line bores (inserted throughout existing 02710 spec)	pp 1, 3-11, 15-end	
		Fixed header--none on p. 2	p. 2	
		Added written approval from Engineer needed where minimum separation with sewer lines cannot be met	3.01H, 4th paragraph	
		Changed minimum distance between M.J. flanges from 2.5 to 2.0 feet	3.01D	
Sanitary Sewer	02712	Added description and requirements of temporary water system, and pay item	3.01L, 4.01 & 4.02	
		Added detail and spec on tapping lined sewer main	2.01C, 3.01E	new dwg 02712-2.01C, current C dwgs changed to D
		Added information on couplings required	2.01G	
		Green tracer wire--changed reference to be consistent with rest of spec book	2.01D	
Storm Drain Pipe and Fittings	02714	Added terms for coordination and cost responsibility re: videoing sewer line	3.01F6 paragraphs 2-4	
		Added section on connecting to existing storm drain, fixed pay item # for "connect to existing 'x' storm drain line" from 02712.4X to 02714.4X	3.01J, 4.01A5 & 4.02A5	
Storm Drain Inlets	02720	Added storm drain inlet for valley gutters (call type D and E)	4.01 & 4.02	new dwg 02720-2.01d

Manholes	02722	Added adjusting rings into new spec	2.01, 3.01, 3.02	revised dwgs 02722-2.01A, -2.01b, -STRMA, 02570-3.01B, 02722-3.02
		Manhole steps: changed minimum projection from 6.5 to 5.75 inches	2.02	
		PVC-lined channel	2.01, 3.01	revised dwgs 02722-2.01A, 2.01B, 2.01C
		Added HS-20 loading requirement for all manholes	2.01 end first paragraph	
Testing, Cleaning and Sterilizing Waterline Systems	02766	Diamonds--not required in pavement except as corrective. Required in non-paved areas	3.08	revised dwgs 02570-3.01a, 02570-3.01b, 02722-3.02
		Added chlorinated water shall be in newly installed water mains max 72 hrs w/o approval from City. All chl water shall be flushed w/in 72 hrs	3.02B.5	
		Coordination section added to add charge for City's time if delayed, other coord. reqs	1.03, 3.01A	
		Added paragraph on contractor testing without the use of valves, if necessary	3.01A, last paragraph	
Engineering Fabric	02895	Fixed equation at end	4.02D	
		Specified Mirafi HP270 for fabric beneath crushed aggregate base course, specification values changed in table for woven separation & stabilization fabric	2.01, Table p. 2	

DIVISION 3 - CONCRETE

Concrete Work	03010	Added "at contractor's expense" to req. of mix design from ind. testing laboratory	1.03B first sentence	
		Water-cement ratio -- called out to include on mix design and on ticket	1.04C.2, 3.15A	
		Added subsection on color pigment	2.03F	
		Added 100 psi strength requirement for flowable fill to table (per 02228)	2.05A	
Concrete Curb and Gutter	03020	Added pay items 03020.30000 and 03020.40000 for temp curb and gutter types A and B	4.01 & 4.02	
		Changed standard details to show curb and gutter flush with adjacent concrete pavement		revised dwg 03020-2.01A, new dwg 03020-2.01b
Concrete Sidewalks, Approaches, Fillets and Double Gutters	03030	Added requirement of "W" and "S" stamps on top back of curb	3.04A last paragraph	
		Fixed double gutter first page--underline of header wrong	p. 1	
		Driveway widths for approaches--changed table consistent with design stds.		revised dwg 03030-3.01k
		Removed incorrect equation from fillet detail		revised dwg 03030-3.01e
Portland Cement Concrete Pavement	03040	Added colored sidewalk pay item, #03030.01X	4.01 & 4.02	
		Included placing and compacting crushed base as subsidiary in double gutter pay item	4.02A.5	
		Modified tiebar placement in roadway. #4 bar, 24" on center, 24" long		dwgs 03040-2.01a,b,d modified
		Specified tie bar depth at 1/2 concrete thickness		dwgs 03040-2.01a,b,d modified
		Specified tie bars at all longitudinal joints in new concrete		dwg 03040-2.01c modified
		Water-cement ratio -- called out to include on ticket	3.09A	
		Added X" colored concrete pay item 03040.01X	4.01 & 4.02	

DIVISION 13 - CORROSION PROTECTION

Corrosion Protection of Plastic Pipe Systems	13900	fixed header	p. 2	
		fixed tracer wire color--make consistent -blue for water green for sewer	2.03.D.1.d, 2.12 A	

DIVISION 26 - LIGHTING

Roadway Decorative Lighting System	26010	Added detail sheet for decorative lighting	[no division 26 in std. spec.]	new dwg 26010-1 added
------------------------------------	-------	--	--------------------------------	-----------------------

GENERAL FORMS

AWARD FORMS

CONSTRUCTION FORMS

Periodic Application for Progress Payment to Contractor		Added language about subcontractor payment in Contractor Cert.	bottom left box	
Warranty		Removed "[contractor]" from header, changed substantial to final completion	end of 1st paragraph	

CLOSEOUT FORMS